



The State of New Hampshire  
**Department of Environmental Services**



**Robert R. Scott, Commissioner**

---

**WETLANDS AND NON-SITE SPECIFIC PERMIT 2021-01513**

**NOTE CONDITIONS**

**PERMITTEE:** NH DEPT OF TRANSPORTATION  
C/O DAVID SCOTT  
7 HAZEN DR  
CONCORD NH 03302

**PROJECT LOCATION** US RTE 4 (MASCOMA VALLEY RD), CANAAN  
TAX MAP #ROW, LOT #ROW

**WATERBODY:** INDIAN RIVER

**APPROVAL DATE:** AUGUST 23, 2021                      **EXPIRATION DATE:** AUGUST 23, 2026

---

Based upon review of permit application 2021-01513 in accordance with RSA 482-A and RSA 485-A:17, the New Hampshire Department of Environmental Services (NHDES) hereby issues this Wetlands and Non-Site Specific Permit. To validate this Permit, signatures of the Permittee and the Principal Contractor are required.

**PERMIT DESCRIPTION:** Temporarily impact 8,526 square feet (SF), including 6,869 SF within the bed and banks of the Indian River (384 linear feet) and 1,657 SF of palustrine emergent wetland for construction access and installation of erosion and dewatering controls associated with repair of the deck, abutments, and wingwalls of NHDOT Bridge No. 169-073 (US RTE 4).

**THIS PERMIT IS SUBJECT TO THE FOLLOWING PROJECT-SPECIFIC CONDITIONS:**

1. In accordance with Env-Wt 307.16, all work shall be done in accordance with the plans for NHDOT State Project No. 42938, US Route 4 over Indian River - Canaan dated July 16, 2021, as received by the NH Department of Environmental Services (NHDES) electronically on July 22, 2021, and with the revised Canaan 42938 Construction Sequence as received by NHDES electronically on August 23, 2021.
2. In accordance with Env-Wt 527.05(a), in addition to complying with all applicable conditions in Env-Wt 307, the permit shall be contingent on review and approval by the department of final stream diversion and erosion control plans that detail the timing and method of stream flow diversion during construction and show temporary siltation, erosion, and turbidity control measures to be implemented.
3. In accordance with Env-Wt 527.05(b), the contractor responsible for completion of the work shall use techniques described in Env-Wq 1504.06, Env-Wq 1504.16, Env-Wq 1505.02, Env-Wq 1506, and Env-Wq 1508.
4. In accordance with Env-Wt 314.03(a), the permittee shall notify the department in writing at least one week prior to commencing any work under the permit.
5. In accordance with Env-Wt 904.02(a)(1), in-stream work shall be done only during low flow or dry conditions, in non-tidal areas.
6. In accordance with Env-Wt 904.02(b), work on stream crossings that requires any work in areas that are subject to flowing water shall maintain normal flows and prevent water quality degradation during the work by using best management practices, such as temporary by-pass pipes, culverts, or cofferdams.
7. All work shall be conducted and maintained in such a way as to protect water quality as required by Rule Env-Wt 307.03(a) through (h).

[www.des.nh.gov](http://www.des.nh.gov)

29 Hazen Drive • PO Box 95 • Concord, NH 03302-0095

NHDES Main Line: (603) 271-3503 • Subsurface Fax: (603) 271-6683 • Wetlands Fax: (603) 271-6588

TDD Access: Relay NH 1 (800) 735-2964

8. In accordance with Env-Wt 307.03(a), no activity shall be conducted in such a way as to cause or contribute to any violation of surface water quality standards specified in RSA 485-A:8 or Env-Wq 1700; ambient groundwater quality standards established under RSA 485-C; limitations on activities in a sanitary protective area established under Env-Dw 302.10 or Env-Dw 305.10; or any provision of RSA 485-A, Env-Wq 1000, RSA 483-B, or Env-Wq 1400 that protects water quality.
9. In accordance with Env-Wt 307.03(b), all work, including management of soil stockpiles, shall be conducted so as to minimize erosion, minimize sediment transfer to surface waters or wetlands, and minimize turbidity in surface waters and wetlands using the techniques described in Env-Wq 1505.02, Env-Wq 1505.04, Env-Wq 1506, and Env-Wq 1508; the applicable BMP manual; or a combination thereof, if the BMP manual provides less protection to jurisdictional areas than the provisions of Env-Wq 1500.
10. In accordance with Env-Wt 307.03(c)(2), water quality control measures shall be comprised of wildlife-friendly erosion control materials if erosion control blankets are utilized; a protected species or habitat has been documented; the proposed work is in or adjacent to a priority resource area (PRA); if specifically requested by Natural Heritage Bureau of the NH DNCR (NHB) or NH Fish and Game Department (NHF&G); or any if combination of the above conditions apply.
11. In accordance with Env-Wt 307.03(c)(3), water quality control measures shall be installed prior to start of work and in accordance with the manufacturer's recommended specifications or, if none, the applicable requirements of Env-Wq 1506 or Env-Wq 1508.
12. In accordance with Env-Wt 307.03(c)(4), water quality control measures shall be capable of minimizing erosion; collecting sediment and suspended and floating materials; and filtering fine sediment.
13. In accordance with Env-Wt 307.03(c)(5), water quality control measures shall be maintained so as to ensure continued effectiveness in minimizing erosion and retaining sediment on-site during and after construction.
14. In accordance with Env-Wt 307.03(c)(6), water quality control measures shall remain in place until all disturbed surfaces are stabilized to a condition in which soils on the site will not experience accelerated or unnatural erosion by achieving and maintaining a minimum of 85% vegetative cover using an erosion control seed mix, whether applied in a blanket or otherwise, that is certified by its manufacturer as not containing any invasive species; or placing and maintaining a minimum of 3 inches of non-erosive material such as stone.
15. In accordance with Env-Wt 307.03(c)(7), temporary water quality control methods shall be removed upon completion of work when compliance with Env-Wt 307.03(c)(6) is achieved.
16. In accordance with Env-Wt 307.03(g)(1), the person in charge of construction equipment shall inspect such equipment for leaking fuel, oil, and hydraulic fluid each day prior to entering surface waters or wetlands or operating in an area where such fluids could reach groundwater, surface waters, or wetlands.
17. In accordance with Env-Wt 307.03(g)(2), the person in charge of construction equipment shall repair any leaks prior to using the equipment in an area where such fluids could reach groundwater, surface waters, or wetlands.
18. In accordance with Env-Wt 307.03(g)(3) and (4), the person in charge of construction equipment shall maintain oil spill kits and diesel fuel spill kits, as applicable to the type(s) and amount(s) of oil and diesel fuel used, on site so as to be readily accessible at all times during construction; and train each equipment operator in the use of the spill kits.
19. In accordance with Env-Wt 307.03(h), equipment shall be staged and refueled outside of jurisdictional areas (unless allowed) and in accordance with Env-Wt 307.15.
20. In accordance with Env-Wt 307.07, all development activities associated with any project shall be conducted in compliance with applicable requirements of RSA 483-B and Env-Wq 1400 during and after construction.
21. All dredging activities shall meet all of the conditions listed in Rule Env-Wt 307.10(a) through (n).
22. In accordance with Env-Wt 307.10(c), turbidity controls shall be installed prior to construction and maintained during construction such that no turbidity escapes the immediate dredge area; and remain in place until suspended particles have settled and water at the work site has returned to normal clarity.
23. All temporary and permanent filling activities shall meet all of the conditions listed in Rule Env-Wt 307.11(a) through (l).
24. In accordance with Env-Wt 307.11(k) and (l), swamp mats shall be properly installed, not dragged into position; and removed immediately upon the completion of work.

25. In accordance with Env-Wt 307.11(g), authorized temporary fill other than swamp mats, construction mats, and corduroy shall be placed on geotextile fabric laid on preconstruction wetland grade.
26. In accordance with Env-Wt 307.11(f), swamp mats and construction mats shall be deemed temporary fill for new authorizations only if they meet the requirements of Env-Wt 307.11(h)(1) and (2).
27. In accordance with Env-Wt 307.11(j), wetlands and surface waters shall be restored to pre-impact conditions and elevation as specified in Env-Wt 307.12(i).
28. Restoration of all temporary impacts shall meet all of the conditions listed in Rule Env-Wt 307.12(a) through (i).
29. In accordance with Env-Wt 307.12(a), within 3 days of final grading or temporary suspension of work in an area that is in or adjacent to surface waters, all exposed soil areas shall be stabilized by seeding and mulching, if during the growing season; or mulching with tackifiers on slopes less than 3:1 or netting and pinning on slopes steeper than 3:1 if not within the growing season.
30. In accordance with Env-Wt 307.12(f), if any temporary impact area that is stabilized with seeding or plantings does not have at least 75% successful establishment of wetlands vegetation after 2 growing seasons, the area shall be replanted or reseeded, as applicable.
31. In accordance with Env-Wt 307.12(i), wetland areas where permanent impacts are not authorized shall be restored to their pre-impact conditions and elevation by replacing the removed soil and vegetation in their pre-construction location and elevation such that post-construction soil layering and vegetation schemes are as close as practicable to pre-construction conditions.
32. In accordance with Env-Wt 307.14(c) and subject to Env-Wt 307.14(e), rocks removed from the bed of a surface water shall be relocated within 10 feet to 20 feet of their current location and at a similar depth.
33. In accordance with Env-Wt 307.15(b), mobile heavy equipment working in wetlands shall not be stored, maintained, or repaired in wetlands, except that repairing or refueling in a wetland is allowed if equipment cannot practicably be removed and secondary containment is provided.
34. In accordance with Env-Wt 307.15(c), where construction requires the operation of heavy equipment in wetlands, the equipment shall either have low ground pressure, namely less than 4 psi, or not be located directly on wetland soils and vegetation; or be placed on timber or swamp mats that are adequate to support the equipment in such a way as to minimize disturbance of wetland soil and vegetation.


**THIS PERMIT IS SUBJECT TO THE FOLLOWING GENERAL CONDITIONS:**

1. Pursuant to RSA 482-A:12, a copy of this permit shall be posted in a secure manner in a prominent place at the site of the approved project.
2. In accordance with Env-Wt 313.01(a)(5), and as required by RSA 482-A:11, II, work shall not infringe on the property rights or unreasonably affect the value or enjoyment of property of abutting owners.
3. In accordance with Env-Wt 314.01, a standard permit shall be signed by the permittee, and the principal contractor who will build or install the project prior to start of construction, and will not be valid until signed.
4. In accordance with Env-Wt 314.03(a), the permittee shall notify the department in writing at least one week prior to commencing any work under this permit.
5. In accordance with Env-Wt 314.08(a), the permittee shall file a completed notice of completion of work and certificate of compliance with the department within 10 working days of completing the work authorized by this permit.
6. In accordance with Env-Wt 314.06, transfer of this permit to a new owner shall require notification to, and approval of, the NHDES.
7. The permit holder shall ensure that work is done in a way that protects water quality per Env-Wt 307.03; protects fisheries and breeding areas per Env-Wt 307.04; protects against invasive species per Env-Wt 307.05; meets dredging activity conditions in Env-Wt 307.10; and meets filling activity conditions in Env-Wt 307.11.
8. This project has been screened for potential impact to known occurrences of protected species and exemplary natural communities in the immediate area. Since many areas have never been surveyed, or only cursory surveys have been performed, unidentified sensitive species or communities may be present. This permit does not absolve the permittee from due diligence in regard to state, local or federal laws regarding such communities or species. This

permit does not authorize in any way the take of threatened or endangered species, as defined by RSA 212-A:2, or of any protected species or exemplary natural communities, as defined in RSA 217-A:3.

9. In accordance with Env-Wt 307.06(a) through (c), no activity shall jeopardize the continued existence of a threatened or endangered species, a species proposed for listing as threatened or endangered, or a designated or proposed critical habitat under the Federal Endangered Species Act, 16 U.S.C. §1531 et seq.; State Endangered Species Conservation Act, RSA 212-A; or New Hampshire Native Plant Protection Act, RSA 217-A.
10. In accordance with Env-Wt 307.02, and in accordance with federal requirements, all work in areas under the jurisdiction of the U.S. Army Corps of Engineers (USACE) shall comply with all conditions of the applicable state general permit.

APPROVED:



Tyler J. Davidson  
Wetlands Specialist, Wetlands Bureau  
Land Resources Management, Water Division

**THE SIGNATURES BELOW ARE REQUIRED TO VALIDATE THIS PERMIT (Env-Wt 314.01).**

---

PERMITTEE SIGNATURE (required)

---

PRINCIPAL CONTRACTOR SIGNATURE (required)